INVITATION TO TENDER "ITT"/ NO. PS20171898 - VANCOUVER LANDFILL – PHASE 4 LIFT 1 LEACHATE COLLECTOR

QUESTIONS AND ANSWERS NO. 1

ISSUED ON NOVEMBER 07, 2017

Q1	**Please confirm payment quantity for line item 2.1 is 400m. Drawings 102 and 103 show total of 692m of 400mm HDPE DR17 solid pipe.**
A1	See Amendment No.1 (AMD 1). Payment Item 2.1 - Leachate Collector Trench c/w 400 mm φ HDPE DR17 Perforated Pipe – quantity revised from 400m to 692m.
Q2	**Please confirm payment quantity for line item 2.2 is 50m. Drawings 102 and 103 show total of 177m of 400mm HDPE DR17 solid pipe.**
A2	See Amendment No.1 (AMD 1). Payment Item 2.2 - Leachate Conveyance Trench c/w 400 mm φ HDPE DR17 Solid Pipe – quantity revised from 50m to 177m.
Q3	**Please confirm if the P-Trap detail on DWG 104 is to be used for the P-Trap located by MH#1 as it appears the P-Trap is ~2.6m in height per profile DWG 102?**
A3	The P-Trap as shown on detail D from DWG 104 is to be used on the north and south P-Traps. The profile view vertical exaggeration is not to scale on DWG 102.

City of Vancouver
453 West 12th Avenue
Vancouver, British Columbia V5Y 1V4 Canada
tel: 3-1-1, Outside Vancouver 604.873.7000 *fax:* n/a
website: vancouver.ca

2017 BC's Top Employers