

### INIVITATION TO TENDER NO. PS20180133

### KERRISDALE COMMUNITY CENTRE DDC CONTROLS UPGRADE

#### **QUESTIONS AND ANSWERS NO. 1**

#### ISSUED ON FEBRUARY 28, 2018

| Q1        | MPZ controllers ok for LC500 replacement?  |
|-----------|--|
| <b>A1</b> | Yes. The Mach ProZone controller is a viable replacement for a LC500 controller.                     |
| Q2        | Valve list shows all valves as 1/2", but some mm sizes are 32mm. Are the mm sizes the correct sizes? |
| A2        | Sizes in mm are the correct ones. 32 mm = 3/4"   |
| Q3        | Are the sizes on the valve schedule line size or valve size?   |
| А3        | Valve sizes.   |
| Q4        | Are radiant heat valves (on VAV's) modulating or 2-position?   |
| A4        | Modulating.  |
| Q5        | Are Belimo zone valves acceptable on Wall fins?  |
| A5        | Contractor to confirm what Belimo model considered for zone valves.                                  |

## INIVITATION TO TENDER NO. PS20180133

## KERRISDALE COMMUNITY CENTRE DDC CONTROLS UPGRADE

# **QUESTIONS AND ANSWERS NO. 1**

| Q6  | Are Belimo CCV valves acceptable?   |
|-----|---|
| A6  | CCV Ball valves are acceptable.   |
| Q7  | Is it acceptable to use temperature/occupancy combo sensors? (As opposed to standalone ceiling mounted)   |
| A7  | No, occupancy sensors shall be independent from temperature sensors.  |
| Q8  | Will building mechanical drawings be available to the controls contractor? (For graphic floor plates)   |
| A8  | Yes, existing mechanical drawings will be provided as existing. There were several renovations DDC contractor to confirm if updated.  |
| Q9  | Is browser-based access required for this upgrade? (MachPro-Web Controller)   |
| А9  | No. A MachPro Web controller will not be necessary for this site. Operator access with be with either client software or through enterprise web server (RC-WebView or Enteliweb). |
| Q10 | There are new actuators, but are new dampers also required?   |
| A10 | New dampers are not required. If existing dampers are discovered defective during installation they are to be raised as a deficiency.   |