

July 19, 2018

**INVITATION TO TENDER "ITT" No. PS20180883  
RODDAN LODGE CONSTRUCTION**

**ADDENDUM NO. 9**

**RE: REVISIONS TO SPECIFICATIONS AND DRAWINGS**

*Please see the revisions by the Consultant in the following pages.*

**Revised specifications as follows:**

Section 08 71 00 Finish Hardware	2018.07.04 2
Section 08 14 00 Wood Doors, NOT ISSUED. Revise 2.4A <b>Hollow Core</b> Suite Interior Doors:	
Section 08 81 00 Glass Glazing, revised 2.7	2018.07.04 8
Section 08 90 00 Louvres and Vents, Delete 2.3 and 2.4	2018.07.04 5
Section 10 11 00 Visual Display Boards, revised 2.3 and 2.4	2018.07.04 3
Section 11 24 29 Facility Fall Protection, NOT ISSUED. Delete 2.1A1.2. Add to 2.1A1:	
<b>.4 DB Cast-in Cage Davit Base: DB4-23203 w/ Aluminum Cover Plate</b>	
BDA Preliminary Design (Insert in Volume 3 Appendices: Appendix E)	2018.07.03 14

**Revised Architectural Drawings as follows:**

- A0.01: NOT ISSUED. New Drawing A5.33 PLAN DETAILS added to ARCHITECTURAL DRAWING LIST
- A2.02: New Plain Detail tags for Building exterior west wall. Plumbing chase enclosure added at Health Office
118. Kitchen layout revisions as indicated.
- A2.05: Roof anchors added to Roof.
- A2.07: Terrace roof anchors deleted. Davit base added.
- A2.08: Terrace wall anchors deleted. Davit base added.
- A2.09: Davit base added to Roof Terrace.
- A2.11: Replace concrete pads with concrete curbs for mechanical RTU's. Add metal guardrail to roof parapet next to mechanical screenwall (near Gridline 4 and between D & G as indicated.

A2.12: Interior Elevations tags added. Corner guard locations added.  
A2.13: Interior Elevations tags added. Corner guard locations added.  
A2.14: Interior Elevations tags added. Corner guard locations added.  
A2.15: Interior Elevations tags added. Corner guard locations added.  
A4.01: Replace concrete pads with concrete curbs for mechanical RTU's on the main Roof.  
A4.04: Replace concrete pads with concrete curbs for mechanical RTU's on the main Roof.  
A5.01: Guardrail added to Detail 1. Canopy glazing clarification.  
A5.11: Revised Detail 5 to show spandrel panel.  
A5.12: NOT ISSUED. Detail 8 revise Note: T.O CONC. SLAB @ L1 EL. 14.65  
A5.33: New Sheet of Plan Details  
A5.55: Notes added to Window & Doors Plan Details 1 to 3. New Details 5 to 7 added.  
A5.61: Detail 2 revised from concrete housekeeping pad to concrete curbs.  
A5.63: New Detail 4 Davit Base added.  
A6.07: Notes added to identify extent of continuous drip edge under Stair S3.  
A6.08: Notes added to identify extent of continuous drip edge under Stair S3.  
A9.01: Dimensions added to Patio Door sliders and Window Type 09B  
A9.02: Revisions to Type 12A, 12B and 12C as noted.  
A10.02: Revised as noted to coordinate Security Drawings & Hardware Spec

**Kitchen Addendum No. 04**

**2018.07.04**

*\*Note: No Kitchen Addendum 1 - 3*

**Structural Addendum No. 02**

**2018.07.04**

**Mechanical Addendum MADD No. 04**

**2018.07.04**

**Electrical Addendum EADD No. 03**

**2018.07.04**

**Security Addendum No. 04**

**2018.07.04**

This addendum must be completed and attached to your Tender form.

If you have already submitted your Tender, this addendum shall be submitted to the Supply Chain Management Office drop box, 4<sup>th</sup> Floor, City of Vancouver, 453 West 12<sup>th</sup> Avenue, Vancouver, British Columbia, Canada, V5Y 1V4. Envelopes submitted by courier or otherwise in-person should be delivered to the same address prior to the Closing Time: 3:00:00 pm Local Vancouver, BC Time, on **July 31, 2018** in an envelope clearly marked "Addendum No. 9 to Invitation to Tender No. PS20180883: Roddan Lodge Construction.

---

NAME OF VENDOR

---

SIGNATURE OF AUTHORIZED SIGNATORY

---

DATE

Donabella Bersabal  
Contracting Specialist