

DECOMMISSIONING THE EXISTING LIGHTING SYSTEM

1.0 Decommissioning the Existing Lighting System

- (a) Existing tunnel lighting system and connected street lighting and the traffic signal shall remain operational throughout the construction
- (b) All existing tunnel luminaires, conductors and conduits shall be removed after the new system is installed and operational
- (c) If existing light must be removed before new system is operational, the Contractor shall implement a traffic management plan for the interim (to be approved by the City of Vancouver)
- (d) The Contractor will decommission and remove all existing materials (conduits, wires, fixtures, Junction boxes, panels etc.) for deconstruction and recycling. The contractor will deconstruct and separate the various (existing) materials to ensure that a high percentage of material is recycled and will not be placed in a landfill. Any new scrap generated during construction will also be dealt with in the same manor. Loads are not stockpiled and are loaded directly into trucks to avoid the mixing of materials.