

**REQUEST FOR PROPOSAL “RFP” NO. PS20170310
CONTRACTOR FOR TEMPORARY FIRE HALL 17**

QUESTIONS AND ANSWERS NO. 4

ISSUED ON JUNE 15, 2017

Q4.1	We understand that the Locution System complete with Rip / Run is supplied by others. Can you please confirm the rough-in requirements?
A4.1	Rip/Run printer is part of Locution System. Electrical contractor is to provide power connection, communication cabling and communication outlet for the system.
Q4.2	Please confirm that the communication system will be done by others and we are to rough-in conduits only.
A4.2	Communication cabling shall be part of electrical contractor scope.
Q4.3	Please provide the structural design importance category for the Fire Truck Shelter and Quarters. Previous tender for Fire Truck Shelter, which was cancelled, did not need to be post disaster rated there is no indication in the new tender documents to confirm or deny this.
A4.3	Post disaster rating is not required.