

INVITATION TO TENDER "ITT" NO. PS20170706  
CONTRACTOR FOR DOUGLAS PARK PLAYGROUND REPLACEMENT

INFORMATION MEETING - 10:00 am, January 9, 2018

QUESTIONS AND ANSWERS NO. 1

ISSUED ON January 15, 2018

Q1	<i>Is the requirement for a trampoline or a multi-spinner?</i>
A1	<p>Eurotramp trampoline - see revised specifications and drawings per AMENDMENT 1:</p> <ul style="list-style-type: none"> <li>• Specification - "11 68 13 Play Equipment (REVISION 2)"</li> <li>• drawing "L-200 LAYOUT AND MATERIALS PLAN (REVISION 2)"</li> <li>• drawing - "L-400 CEDAR FENCING &amp; EUROTRAMP DETAIL"</li> </ul> <p>Trampoline, concrete base and surrounding rubber impact protection system supplied and installed by RecTec Industries (Sales: Jeff Kuby, 604 940 0067) , or approved equivalent.</p>
Q2	<i>Are there proposed grades for the playground curb etc.?</i>
A2	See AMENDMENT 1 - "L-300 Grading and Drainage Plan (REVISION 2)". There have been some changes to the grades with more spot elevations added for clarity.
Q3	<i>Section BB referenced on L-200 does not correspond to detail shown on L-503. Please confirm section reference.</i>
A3	See AMENDMENT 1 - drawing "L-200 MATERIALS LAYOUT PLAN (REVISION 2)". Page number and section identification letters have been corrected.
Q4	<i>Where is the preferred site access?</i>
A4	<p>There are two available options:</p> <ol style="list-style-type: none"> <li>1. Along the existing path. A 1.5m wide area of path needs to remain accessible for the preschool exit</li> <li>2. West of the wading pool (existing tree root zone would have to be protected)</li> </ol> <p>Please clarify your site access approach.</p>

**INVITATION TO TENDER "ITT" NO. PS20170706  
CONTRACTOR FOR DOUGLAS PARK PLAYGROUND REPLACEMENT**

**INFORMATION MEETING - 10:00 am, January 9, 2018**

<b>Q5</b>	Are there specifications and drawings to show the extent of the wood split rail fence from the form of tender?
<b>A5</b>	The split rail fence is only around the "outdoor classroom" next to the community centre - See details per AMENDMENT 1 - Drawing - " L 400 CEDAR FENCING & EUROTRAMP DETAIL " .
<b>Q6</b>	<i>Is tree protection required?</i>
<b>A6</b>	Yes, tree protection is required. Park Board will provide an arborist for any work required on tree canopies.
<b>Q7</b>	<i>Please clarify the irrigation requirements for the project; the irrigation specifications are provided but the extent of the system is not indicated, nor a line item in the form of tender.</i>
<b>A7</b>	There is no irrigation in the contract. We have asked for a price to add a quick coupler as per detail 5 on drawing L-506 to the contract. This would be supplied from the water line to the children's water play spigot.
<b>Q8</b>	<i>Please clarify the planting requirements for the project. Is the plant material to be supplied and installed by the City of Vancouver, and maintained per the maintenance spec?</i>
<b>A8</b>	There is no planting required. Only planting bed preparation areas (as per detail 5 drawing "L-503 DETAILS")
<b>Q9</b>	<i>Is the seating shown on L-200 on the north side of playground "edge seating" shown in Detail 3 and 5 on L-501?</i>
<b>A9</b>	Yes, the note has been corrected on revised "L-200 MATERIALS LAYOUT PLAN (REVISION 2)"
<b>Q10</b>	<i>What is the colour requirement for the play tiles?</i>
<b>A10</b>	50/50 mix blue/black for the rubber pathway and tan/black for southern course "beaver dam". The thickness of surface to be 2" except where varies as shown on Drawing "L-200 MATERIALS LAYOUT PLAN (REVISION 2)"
<b>Q11</b>	<i>What is the colour requirement for the water fountain?</i>
<b>A11</b>	Silver

**INVITATION TO TENDER "ITT" NO. PS20170706  
CONTRACTOR FOR DOUGLAS PARK PLAYGROUND REPLACEMENT**

**INFORMATION MEETING - 10:00 am, January 9, 2018**

<b>Q12</b>	<i>Please clarify the supply and installation of the edge seating. Which parts will be supplied by the City?</i>
<b>A12</b>	<p>The City will supply the steel brackets. See details 3 and 5 of sheet "L501 DETAILS"</p> <p>Examples of the edge seat can be seen at the following Park Board playgrounds:</p> <ul style="list-style-type: none"> <li>• Nanaimo Park Playground</li> <li>• Trout Lake Community Centre Playground</li> </ul>
<b>Q13</b>	<i>Please clarify the requirement for the boulder.</i>
<b>A13</b>	The City will supply the boulders from Kent Yard and will load boulders onto Contractor's truck.
<b>Q14</b>	<i>Is the Contractor responsible for relocating the light pole on south side of playground?</i>
<b>A14</b>	No, the light pole will be relocated by Park Board.
<b>Q15</b>	<i>Is the playground gate entrance to remain at the existing location?</i>
<b>A15</b>	Yes, very close to the existing location.
<b>Q16</b>	<i>Is the contractor responsible for installing the concrete pads for the bench?</i>
<b>A16</b>	Yes, concrete pads only. Benches and picnic tables will be installed by Park Board after project completion.
<b>Q17</b>	<i>Is the Contractor responsible for reinstalling the zipline?</i>
<b>A17</b>	Yes, contractor to remove existing zip line. Park Board to take away for painting, then return to site for contractor to reinstall in new location
<b>Q18</b>	<i>Will any of the rubber tiles be reused?</i>
<b>A18</b>	Yes, some of the existing rubber tiles will be reused and installed under the swing 3m swing and the arched swing. See drawing "L-200 MATERIALS LAYOUT PLAN"