

**INVITATION TO TENDER "ITT" NO. PS20180805  
CONSTRUCTION SERVICES FOR TRENCHLESS SEWER**

**QUESTIONS AND ANSWERS NO. 2**

ISSUED ON SEPTEMBER 19, 2018

Q1	I would like to know if the existing 900 combined sewer will be completely deactivated prior to trenchless construction?
A1	The combined sewer will be bypassed and removed from the entry and exit pits by City forces.
Q2	Can SWSP casings be used and the CCGRP be slipped inside the steel casing?
A2	The intent of the design was to maximize the distance to, and minimize the potential for disturbance to, the existing sensitive Fortis and Metro Vancouver infrastructure. Spiral-Welded Steel Pipe (SWSP) casings would necessarily be larger than the Centrifugally Cast Glassfibre Reinforced Plastic (CCGRP) carriers and so decrease the distance to these existing utilities.  Both steel or Hobas pipe will be accepted. .
Q3	If steel casings can be installed, can an alternate carrier pipe be used?
A3	Yes.
Q4	List of General Contractors interested in this tender?
Q5	The City does not hold a planholders list for the ITT.