INVITATION TO TENDER "ITT" NO. PS20181796

Echelon 3rd Floor Tenant Improvements

ADDENDUM # 3

RE: SPECIFICATIONS

.1 Section 01 10 00 Summary

Delete:
10.2 Asbestos Discovery - Asbestos containing gypsum wall board ceiling around the perimeter of the building core will be removed by the Building Owner.

.2 Section 06 40 00 Architectural Woodwork
Specification Section 2.2.7 Plastic Laminate Schedule
Delete:
.1 Nevamar Macchiato WF0011T Textured (Vertical Grain Installation) for all cabinets.

Add:
.1 Nevamar Macchiato WF0011T Textured (Vertical Grain Installation) for all cabinets except Reception Counter.
.2 Formica Microdot Finish Black Noir 909-MC for Reception Counter facing Front Desk 301
.3 Arborite Elegant White CE5 S-550 GL for Reception Counter facing Lobby 300

RE: REFERENCE DRAWINGS

Architectural
.1 ***Change*** building address from 539 W 8th to 575 W 8th.

Structural
.1 ***Change*** building address from 539 W 8th to 575 W 8th.

Mechanical
.1 ***Change*** building address from 539 W 8th to 575 W 8th.

Electrical
.1 ***Change*** building address form 539 W 8th to 575 W 8th.

City of Vancouver, Finance, Risk and Supply Chain Management
453 West 12th Avenue
Vancouver, British Columbia V5Y 1V4 Canada
tel: 604.873.7263 *fax:* 604.873.7057
website: vancouver.ca

INVITATION TO TENDER PS20181796
Echelon 3rd Floor Tenant Improvements
Addendum # 3

RE: DRAWINGS

A-05 ***Add*:**

Ceiling Construction Notes:

1. All ceiling height to be same as existing at approximately 2585 high U.N.O.
2. Also refer to Mechanical and Electrical Drawings for scope of work.

A-13 ***Add:***

Finishes Notes:
1. Writable surface to be 1.2m high installed 900mm from the floor.

END OF ADDENDUM 3.