

INVITATION TO TENDER ("ITT") NO. PS20200764
CONTRACTOR FOR BEACONSFIELD PARK PLAYGROUND REPLACEMENT

QUESTIONS AND ANSWERS NO. 2

ISSUED ON AUGUST 19, 2020

Q1	L1.4- Please confirm all pipe is 100mm diameter
A1	Perforated Pipe: 100mm dia. CSA SDR-35 Rigid Perforated Drain Pipe. Solid Pipe: 250 mm dia. SDR 35 Rigid Non Perforated Drain Pipe. This is as per specifications.
Q2	L1.3-P1 references natural concrete w/ light broom finish, L2.1 references an exposed aggregate finish - Please clarify what the finish of P1 is.
A2	Light Broom
Q3	Form of Tender- item #4.2 references asphalt, no asphalt appears on L1.3 - Please confirm there is no asphalt paving in the scope of work.
A3	No 'new' asphalt paving. Tenderer is responsible to re/re existing asphalt edge where existing edge of playground is demolished.
Q4	L1.5- Tree list references locally approved available product, spec references western north America as the search area- Confirm the search area is the lower mainland.
A4	Under current circumstances a search limited to Lower Mainland is acceptable.