

**INVITATION TO TENDER (“ITT”) No. PS20210981
CONTRACTOR FOR NEIGHBOURHOOD ENERGY UTILITY (NEU) FALSE CREEK ENERGY
CENTRE (FCEC) SITE PREPARATION FOR CONSTRUCTION**

QUESTIONS AND ANSWERS NO. 5

ISSUED ON: November 25, 2021

Q5.1	We assume that the supply of the neoprene pads and anchor rods are the only items required for this scope of work on our end. Shall we allow for supply of the rest of the base plate assembly shown on drawings 028-12838-000 and 028-12818-000 by York International Corporation or will this kit will be supplied directly by them?
A5.1	The supply of the neoprene pads and anchor rods are the only items required for this scope of work. The base plate assembly will be attached to the feet of the chillers when they arrive. Note that the marking up and drilling of the holes is also included in this scope of work.

END OF Q&A No. 5