



**REQUEST FOR PROPOSAL No. PS20220421
CONTRACTOR SERVICES FOR LANGARA GOLF CLUBHOUSE ROOF REPLACEMENT
QUESTIONS AND ANSWERS NO. 2**

ISSUED ON: April 8, 2022

<p>Q1</p>	<p>Could we please get confirmation of where interior protection will be required? We know that the vaulted ceilings at the steep slope locations will require the protection. But we are unsure about the kitchen location, and under the flat roof area 2.1 and 2.2?</p>
<p>A1</p>	<p>Per the specifications, interior protection is required within the kitchen areas. See attached interior photos for reference.</p> 



	
Q2	It was mentioned at the site review that IRC was going to amend the details for the Boston ridge.
A2	Contractor is to ignore the existing wood blocking shown, and is to assume there is only one piece of 2x wood blocking laying flat on the sloped roof surface. Supply and install new wood blocking to suit the specified height, per Detail VHSU801.