


- NOTES:
- AREAS OF THIN SACRIFICIAL TOPPING IN THE REPAIR BOUNDARY OR SACRIFICIAL TOPPING COMPLETELY MISSING
 - PERIMETER CUT = 97.1m
 - AREA = 94.5m²
 - 25mm GENERAL THICKNESS, EXCEPT BY EDGES WHERE IT IS BEING TIED IN AND SOME AREAS MAY BE HIGHER OR LOWER FOR DRAINAGE TO WORK
 - MAIN BONDING AGENT = ???
 - MAIN CONCRETE = EUCLID EUCOFLOOR 404
 - APPLY TOPPING SCREEDING TOWARDS EDGES AND DRAINS
 - CURING AGENT = EUCC AQUA CURE-VDX
 - PRE-CONSTRUCTION SURVEY OF EXISTING WORN OUT SURFACE DONE ON MAY 2020
 - SURVEY CONTROL POINTS (SEE ENG - TLO - VSTS - Infrastructure - Survey Reference Points)
 - SURVEY AS BUILT SURFACE AFTER CONSTRUCTION
 - ADD YELLOW STRIP = QUARTZ FLOORING, DEGACLAD CO, METHACRYLATE, BRIGHT YELLOW
 - CONSTRUCTION IS PLANNED IN 2 PHASES:
 - PHASE 1: DIRECT DUMP CHUTE AREA (I.E. THE NORTHERNMOST AND WESTERNMOST AREAS)
 - PHASE 2: BY THE PIT (I.E. THE THREE EASTERN AREAS)
 - OPERATE ON A SMALL FOOTPRINT (MAKE SURE THAT THE OTHER AREA STILL REMAINS OPERATIONAL)
 - BOTH PHASES TO BE COMPLETED ON WEEKENDS, THE START TIME CAN BE AS EARLY AS 3AM ON SATURDAY AND THE END TIME CAN BE AS LATE AS MIDNIGHT ON SUNDAY (IT IS ACCEPTABLE TO INSTALL THE YELLOW STRIP ON MONDAY MORNING IF DESIRED)
 - GRIND 19mm DEEP AT CUT EDGE TO 9mm ON REPAIR SIDE BY 1m WIDE ALL AROUND (SEE DETAIL A)
 - SAW CUT 13mm WIDE BY 19mm DEEP EDGE AFTER GRINDING TO CREATE A CLEAN EDGE
 - SURFACE PREP INCLUDES: GRINDING, WASHING, PRESSURE WASHING WITH SPINNING NOZZLE, DRYING WITH LEAF BLOWERS AND TORCHES, AND ROLLING ON ACETONE
 - GRIND UNTIL SOUND SURFACE REMAINS AND AT LEAST 5mm DEEP FOR ROUGHENING EVEN IN THE WORN OUT AREAS
 - FALL PROTECTION RAILINGS ARE AVAILABLE ON SITE, THEY ARE TO BE WELDED TO THE BUMPER BLOCKS WITH MINIMUM 6mm FILLET WELD ALL AROUND AT EACH LEG, EACH RAILING IS ~2.5m LONG, THEY ARE TO BE REMOVED PROMPTLY AFTER CONSTRUCTION (WITHIN 24HRS)
 - FOLLOW MANUFACTURER SPECIFICATIONS
 - MATERIALS SUPPLIED BY CITY: BONDING AGENT, CONCRETE BAGS, AND CURING AGENT



NO.	DATE	REVISION	BY	CHK
A	20CT2018	ISSUED FOR REVIEW		

BRANCH	INITIALS	DATE
CHECKED		
CHECKED		

UNITS: METRES
DATUM: UTM NAD 83 ZONE10



ENGINEERING SERVICES

**ENG - TLO - VSTS
COMMERCIAL SIDE TIPPING
FLOOR REPAIRS 2020**

DIV./BR. TRANSFER & LANDFILL OPS.
DATE: 31JUL2020 DESIGN: J.SOB.
DWG: J.SOBE. CHK: K.JHAJJ
REFS: A3,S3,TLO106,TLO160

SCALE:	1:125(H) 1:125(V)
DIRECTORY:	Y:\LANDFILL ENG - TLO - drawings
DWG. NO.	TLO218
SHEET...1...OF...1...	REVISION:.....A.....

THIS PRINT SUPERSEDES ALL PRINTS OF THIS DRAWING BEARING PREVIOUS REVISION NUMBERS